

2013 PCI Design Awards Winner Best Total Precast Concrete Bridge

Route 112 Bridge over the Kearney Brook, Worthington, Massachusetts

The Route 112 Bridge over Kearney Brook in Worthington, Mass., is part of the state's multi-billion-dollar, eight-year accelerated bridge program to fix bridges that have been deemed structurally deficient. It is also one of the first bridges in Massachusetts built with precast concrete abutments, though it surely won't be the last.

"The goal of the project was to reduce road user impacts by reducing the construction time of the bridge," says Michael Culmo, vice president of structures and transportation for CME Associates in East Hartford, Conn. By choosing an all-precast concrete solution, the designers were able to deliver a high-performance, cost-effective bridge in far less time than a traditional design.



Setting first footing piece



Setting first wingwall



Setting abutment pieces

In traditional bridge construction projects, the Massachusetts DOT would build the structure in stages over two years, Culmo says, but one of the goals of the accelerated bridge program is to accelerate construction so that all lanes of traf-

fic are open before the winter shutdown. Designers were able to accelerate construction substantially by replacing the deteriorated single-span steel bridge with a more durable prestressed, precast concrete span that features a two-lane

roadway curved with a radius of 920 ft (280 m).

"Precast concrete for all portions of the bridge is the tool that allows this approach to work," Culmo says. "By prefabricating the ele-

(continued on page 2)

Route 113 Bridge *(continued from page 1)*

ments off-site in a fabrication plant, the majority of the construction is completed before a shovel is placed in the ground, and construction was completed in 60 calendar days.”

Erection of the bridge could have been accomplished in even less time, Culmo says; however that would have led to cost increases. “The goal of this project was to build in a reasonably fast time frame, balancing construction speed with cost-effectiveness,” he says.



Setting NEXT 32F beams

The only significant cast-in-place concrete on the project was the bridge deck topping. To simplify that process, the team used Northeast Extreme Tee (NEXT) beams as the deck forms, which meant that the contractor simply had to form the sides and ends of the deck. The NEXT beam was developed for the purpose of promoting greater uniformity among DOTs, engineers, and the precast concrete industry of the Northeast with respect to planning, designing, fab-



Next Beams installed on bearing pads

ricating, and constructing highway bridges with the Federal Highway Administration’s philosophy of accelerated bridge construction.

During construction, the team placed the full 8 in. (200 mm) reinforced, high-performance concrete deck on top of the 4 in. (100 mm) thick top flange of the beam. “This technically results in a deck thickness of 12 in. (300 mm), which will provide a very durable, long-lasting structure,” Culmo says.



Setting approach slabs

It’s also cost effective. “Preliminary investigations by several fabricators indicate that the NEXT beams could be as much as 40% less expensive than traditional beam slab bridges,” Culmo says. The savings is realized by simplifying the fabrication process, reducing the number of elements that need to be handled, and eliminating traditional deck forming. “The lack of forming and form stripping can offset the cost of additional concrete used in the deck.”

Thanks to Lee Edwards, Dailey Precast, for the photos and facts: This bridge consists of 8 footing pieces, 6 abutment wall sections, 4 wingwalls, 4 guardrail transition bases, 8 approach slabs, and 3 NEXT 32F Beams with integral backwall cast on each end.

PROJECT CREDITS

Owner: Massachusetts Department of Transportation, Boston, Mass.

Engineer of Record: CME Associates Inc., East Hartford, Conn. (also Photo Credit)
 Precaster: William E. Dailey Precast LLC, Shaftsbury, Vt.
 Precast Concrete Specialty Engineer: Calderwood Engineering, Richmond, Maine
 Contractor: J. H. Maxymillian Inc., Pittsfield, Mass.
 Total Cost: \$900,000
 Bridge Length: 64 ft. 6 in. (19.7 m)
 Story and photos taken from: *2013 PCI Design Awards*

Welcome Ronald Thornton, PE, *next PCANY Executive Director*


Starting January 1, Ron will take over for the “retiring” Carl Buchman. Since Carl lives in Rochester, and Ron lives in Binghamton, look for many detail changes to be announced, such as a new mailing address, phone numbers, etc. If you need to reach Ron sooner, his phone is 607-595-1636, email is rthornton2@stny.rr.com, and address is 31 Riverview Ave, Binghamton, NY 13904.

Precast Reservoir Covers Upgrades Letchworth State Park

Letchworth State Park was looking to replace the wood roofs over three of their water reservoirs. The issue was the new roofs needed to be water tight, and with normal planks, the expansion and contraction of so many pieces with an overlay was a concern.

Lakelands approached the engineers prior to the bid for a value engineered design to reduce the

planned joints and the overall cost of on-site work by making custom roofs that could be wider, reducing the number of joints. The new design also incorporated an overhang of the reservoir which would have been cast in the field by the General Contractor, CCS Pipeline.



With the reservoirs having a clear span of 25'-0" the roofs were voided in the center to reduce weight allowing the contractor to handle the roofs with two

excavators, tracking the roofs up the mountain and setting them on preset shims.



The joints were then sealed with backer rod, caulk, 3" butyl sealant and a galvanized tin cap screwed to galvanized dovetail cast on either side of the joints. All five sections of this reservoir unit were delivered and set in one day.

Thanks to Chad Bond, Lakelands Concrete Products Inc., for this article and the photos.

Metro Fire Station, Nashville, TN, Storm Capture Detention System

To detain stormwater runoff at the Metro Fire Station #21, the Metropolitan Government of Nashville and Davidson county elected to remove an aboveground detention pond and construct an underground stormwater detention system to gain back valuable land for parking during the recent replacement of the facility. In the final design, Oldcastle Precast's Storm Capture® stormwater management system was chosen and subsequently constructed under the entrance road, since it reduced the detention system width and overall footprint by over 40%, and easily fit under the fire station roadway. For additional information, go to www.stormcapture.com/content/pdfs/CaseStudy_OldcastlePrecast_FireStation21.pdf.



In the final design, Oldcastle Precast's Storm Capture® stormwater management system was chosen and subsequently constructed under the entrance road, since it reduced the detention system width and overall footprint by over 40%, and easily fit under the fire station roadway. For additional information, go to www.stormcapture.com/content/pdfs/CaseStudy_OldcastlePrecast_FireStation21.pdf.

Precast Concrete Association of New York, Inc.

2829 East Avenue
Rochester, NY 14610
Tel: 585-249-9564 • Fax: 585-381-0945
Email: pcany@aol.com
Web: www.pcany.org

PRODUCER MEMBERS

A & R Concrete Products, New Windsor, NY, 845-562-0640
Bayshore Concrete Products, Cape Charles, VA, 757-331-2300
Binghamton Precast & Supply, Binghamton, NY, 607-722-0334
Camp Precast Concrete Products, Milton, VT, 802-893-2407
J.P. Carrara & Sons, Middlebury, VT, 802-388-6361
Coastal Pipeline Products Corp., Calverton, NY, 631-369-4000
Dailey Precast, Shaftsbury, VT, 802-442-4418
The Fort Miller Co., Inc., Schuylerville, NY, 518-695-5000
Jefferson Concrete Corp., Watertown, NY, 315-788-4171
Kistner Concrete Products, East Pembroke, NY, 585-762-8216
Lakelands Concrete Products, Inc., Lima, NY, 585-624-1990
LHV Precast, Kingston, NY, 845-336-8880
Oldcastle Precast, South Bethlehem, NY, 518-767-2116
Oldcastle Precast Inc., Middle Island, NY, 631-924-7400
Oldcastle Precast Inc., Rehoboth, MA, 508-336-7600
Roman Stone Construction Co., Bay Shore, NY, 631-667-0566
Sunnycrest Inc., Auburn, NY, 315-252-7214
United Concrete Products, Inc., Yalesville, CT
LC Whitford Materials, Co., Inc., Wellsville, NY, 585-593-2741

SEPTIC TANK PRODUCER MEMBERS

Binghamton Precast & Supply, Binghamton, NY, 607-722-0334
The Fort Miller Co., Inc., Schuylerville, NY, 518-695-5000
Guardian Concrete Products, Schenectady, NY, 518-372-0080
Jefferson Concrete Corp., Watertown, NY, 315-788-4171
Keeler Vault Co., Inc., Hudson, NY, 518-851-6281
Kistner Concrete Products, East Pembroke, NY, 585-762-8216
Mid Hudson Concrete Products Inc, Cold Spring, NY 845-265-3265
Sunnycrest Inc., Auburn, NY, 315-252-7214
Zeiser Wilbert Vault, Elmira, NY, 607-733-0568
United Concrete Products, Inc, Yalesville, CT 203-269-3119

ASSOCIATE MEMBERS

A-Lok Products, Inc., Tullytown, PA, 800-822-2565
Amcrete Products, Newburgh, NY, 845-562-0010
American Spacer Technologies, Inc., Hudson, NY, 800-424-8557
BASF Admixtures, Halfmoon, NY, 518-669-8755
Buzzi Unicem USA, Stockertown, PA, 610-746-6224
Cemex, Inc., Wampum, PA, 724-535-4311
Chase Specialty Coatings, Pittsburgh, PA, 412-828-1500

Concrete Sealants, Inc., Royersford, PA, 610-948-7867
East Jordan Iron Works, Newark, NJ 973-350-0600
Eastern States Steel Corp., Upper Saddle River, NJ, 800-327-8335
Engineered Wire Products, Upper Sandusky, OH, 800-842-8381
Eriksson Technologies, Inc., Tampa, FL, 813-989-3317
Essex Cement Company, Port Newark, NJ, 973-344-5903
Essroc Cement, Nazareth, PA, 610-746-3109
The Euclid Chemical Co., Saratoga Springs, NY, 518-376-0871
Federal White Cement Inc., Emmaus, PA, 610-966-9481
Forta Corporation, Grove City, PA, 800-245-0306
W R Grace, Saratoga Springs, NY 585-662-9552
Haarup North America, Inc., Portland, OR, 503-954-1718
W.P. Hiltz & Co, Roanoke, VA 800-227-6798
Holcim (US) Inc., Saratoga Springs, NY, 518-376-0871
Jepco Sales, Royersford, PA, 610-948-7867
JVI, Inc., Lincolnwood, IL, 800-742-8127
Keystone Cement Company, Exton, PA, 610-837-2100
Lafarge North America, Westborough, MA, 508-366-9001
Lehigh Cement Company, Glens Falls, NY, 518-792-1137 x 303
M+P Labs, Schenectady, NY, 518-382-0082
Meadow Burke, Billerica, MA
Mixer Systems, Pewaukee, WI, 860-798-7248
Northeast Solite Corp., Saugerties, NY, 845-246-2646
A L Patterson, Fairless Hills, PA, 800-332-7090
Peikko USA, Sharon Hill, PA, 484-866-5707
Polylok, Inc./Zabel, Wallingford, CT, 800-765-9565
Quinn Consulting, Bladensburg, MD
Riefler Construction Products, Bladell, NY, 716-332-6283
St. Mary's Cement Company, Cleveland, OH, 216-579-1911
Sika Corporation, Lyndhurst, NJ, 302-218-4987
Spillman Co., Columbus OH, 614-444-2184
Splice Sleeve North America, Livonia, MI, 734-838-0420
Superior Precast Consulting, Inc., Ardmore, PA, 610-715-1969
Syracuse Casting Sales Co., Cicero, NY, 315-699-2601
Trelleborg Pipe Seals Milford, Inc., Milford, NH, 800-626-2180
Tuf-Tite, Inc., Lake Zurich, IL, 847-550-1011

PROFESSIONAL MEMBERS

Advance Testing, Campbell Hall, NY, 845-496-1600
AECOM, Latham, NY, 518-951-2200
Atlantic Testing Laboratories, Clifton Park, NY, 518-383-9144
Barton & Loguidice, PC, Syracuse, NY, 315-457-5200
A.S. Bell Engineering, PC, Slingerlands, NY, 518-357-0313
Bergmann Associates, Inc., Rochester, NY, 585-232-5135
Bernier, Carr & Associates, Watertown, NY, 515-782-8130
A L Blades & Sons, Inc., Hornell, NY, 607-324-3636
C & S Engineers, Inc., Syracuse, NY, 518-455-2000
CDM Smith, Syracuse, NY, 315-434-3229
Clark Patterson Lee, Rochester, NY, 585-454-7600
Clough Harbour & Assoc. LLP, Albany, NY, 518-453-3961
Collins Engineering Inc., Albany, NY, 518-436-0392

Concrete Engineering Solutions, LLC, 101 Pine View Estates, Mountain Top, PA 1870, 570-868-2081
Delta Engineers, Architects and Land Surveyors, P.C., Endwell, NY, 607-231-6600
Dewberry, New York, NY, 212-685-0900
Didonato Associates PE, PC, Buffalo, NY, 716-656-1900
Edwards & Kelcey Engrs. Inc., Saratoga Springs, NY, 518-584-9733
Erdman Anthony, Rochester, NY, 585-427-8888 x 419
Eriksson Technologies, Inc., Tampa, FL, 813-989-3317
Fisher Associates PE, LS, PC, Rochester, NY, 585-334-1310
Greenman-Pedersen, Inc., Buffalo, NY, 716-633-4844
Hunt Engr Arch Surveyors PC, Horseheads, NY, 607-358-1000
D.R. Johnson & Associates, LLC, Dover, NJ, 973-328-2354
Keystone Associates, LLC, Binghamton, NY, 607-722-1100
LaBella Associates, PC, Rochester, NY, 585-454-6110
Lamont Engineers, PC, Cobleskill, NY, 518-234-4028
Lancaster Development, Richmondville, NY
M + W Group, Arthur Palmer, Watertown, NY, 518-235-3647
Maser Consulting, Chestnut Ridge, NY, 845-352-0411
McFarland-Johnson, Inc., Binghamton, NY, 607-723-9421
O'Neill Consulting, Spring Lake, NJ, 732-974-0129
Popli Consulting Engineers, Penfield, NY, 585-388-2060
Ravi Engineering & Surveying, P.C., Rochester, NY 585-223-3660
Ryan-Biggs Assoc., P.C., Troy, NY, 518-272-6266
R Samsel Engineers, Henrietta, NY, 585-334-5549
Shumaker Consulting Engineering & Land Surveying, PC, Binghamton, NY, 607-798-8081
Simpson Gumpertz & Heger, Inc., Waltham, MA, 781-907-9000
SJB Services, Inc., Hamburg, NY, 716-649-8110
Slocum, DeAngelus & Associates, PC, Latham, NY, 518-763-6000
Steuben County DPW, Bath, NY, 607-664-2479
Transtech Systems, Schenectady, NY, 518-372-4067
VHB, 100 Great Oaks Blvd., Suite 109, Albany, NY 12203, 518-452-0300
Watson Engineering, PC, Owego, NY, 607-223-4900
Watts Architecture & Engineering, PC, Buffalo, NY, 716-206-1500
WSP-Sells, Briarcliff Manor, NY, 914-747-1120

OFFICERS, DIRECTORS AND STAFF

President: Todd Clarke, Lakelands Concrete Products Inc.
Vice President: Bob Willis, LHV Precast Inc.
Secretary: Kevin Balachick, Binghamton Precast & Supply
Treasurer: Kevin Balachick, Binghamton Precast & Supply
Immediate Past President: Mike Weigand, J.P. Carrara & Sons, Inc.
Associate Member Director: Bruce Houser, Polylok, Inc./Zabel
Professional Member Director: Doug VanDeusen, Lamont Engineers, P.C.
Septic Tank Group Director: Ken Kistner, Kistner Concrete Products, Inc.
NECSA Director: Richard Sullivan, Lehigh Cement
Executive Director: Carl Buchman, PCANY, 585-249-9564